

**പതിനാലാം കേരള നിയമസഭ
പതിനാലാം സമ്മേളനം**

നക്ഷത്ര ചിഹ്നമിടാത്ത ചോദ്യം നം. 959

30-01-2019-ലെ മറുപടി

മലപ്പുറം ജില്ലയിൽ പ്രളയക്കെടുതികൾ മൂലം ഉണ്ടായ നാശനഷ്ടങ്ങൾ

ചോദ്യം		മറുപടി	
ശ്രീ. പി.ഉബൈദുള്ള		കെ. കൃഷ്ണൻകുട്ടി (ജലവിഭവ വകുപ്പുമന്ത്രി)	
(എ)	<p>പ്രളയക്കെടുതികൾ മൂലം മലപ്പുറം ജില്ലയിൽ ഉണ്ടായ നാശനഷ്ടങ്ങളുടെ കണക്കുകൾ ജലവിഭവ വകുപ്പ് തയ്യാറാക്കിയിട്ടുണ്ടോ; വിശദാംശം നൽകാമോ;</p>	(എ)	<p>ഉണ്ട്. ജലസേചന വകുപ്പിലെ ബണ്ടുകൾ, ഗൈലേറ്റുകൾ, ലിഫ്റ്റ് ഇറിഗേഷൻ സ്കീമുകൾ മറ്റ് നിർമ്മിതികൾ എന്നിവയ്ക്കുണ്ടായ നാശനഷ്ടം പരിഹരിക്കുന്നതിനായി മലപ്പുറം ജില്ലയിൽ 52.08 കോടി രൂപ കണക്കാക്കിയിട്ടുണ്ട്.</p> <p>മലപ്പുറം ജില്ലയിൽ പ്രളയക്കെടുതിമൂലം കേരള ജല അതോറിറ്റിക്ക് 313.05 ലക്ഷം രൂപയുടെ നാശനഷ്ടങ്ങൾ ഉണ്ടായിട്ടുണ്ട്. വിശദാംശം അനുബന്ധമായി ചേർത്തിരിക്കുന്നു. ഭൂജലവകുപ്പിന് 60993 രൂപയുടെ നാശനഷ്ടങ്ങൾ ഉണ്ടായിട്ടുണ്ട്.</p> <p>മലപ്പുറം ജില്ലയിൽ ജലനിധി പദ്ധതി നടപ്പിലാക്കുന്ന കരുവാരക്കണ്ട്, കുറ്റിപ്പുറം, ചോക്കാട്, മേലാറ്റൂർ, പറപ്പൂർ, ഊർങ്ങാട്ടിരി എന്നീ പഞ്ചായത്തുകളിലെ 31 സ്കീമുകളെയാണ് പ്രളയക്കെടുതി ബാധിച്ചിട്ടുള്ളത്. 31 സ്കീമുകളുടെ പുനഃസ്ഥാപനത്തിനുള്ള എസ്റ്റിമേറ്റ് തുക 38.29 ലക്ഷം രൂപയാണ്. അവയുടെ പുനരുദ്ധാരണ പ്രവർത്തനങ്ങളുടെ പ്രാരംഭ നടപടികൾ ആരംഭിച്ചിട്ടുണ്ട്.</p>
(ബി)	<p>പുനരധിവാസ പ്രവർത്തനങ്ങൾക്കായി നാളിതുവരെ മേജർ, മൈനർ ഇറിഗേഷൻ വകുപ്പുകൾ തയ്യാറാക്കിയ പദ്ധതികളുടെയും ചെലവഴിച്ച തുകയുടെയും വിശദാംശങ്ങൾ ലഭ്യമാക്കാമോ?</p>	(ബി)	<p>മലപ്പുറം ജില്ലയിലെ പ്രളയത്തെത്തുടർന്നുണ്ടായ പുനരധിവാസ പ്രവർത്തനങ്ങൾക്കായി എം.ഐ ഡിവിഷനിലേയ്ക്ക് പ്ലാൻ ഫണ്ടിൽ ഉൾപ്പെടുത്തി 14 ലിഫ്റ്റ് ഇറിഗേഷൻ സ്കീമുകൾക്ക് 177.74 ലക്ഷം രൂപയുടെ ഭരണാനുമതി നൽകിയിട്ടുണ്ട്. ഇതുകൂടാതെ Repair to MI structures എന്ന plan head ൽ ഉൾപ്പെടുത്തി 81.83 ലക്ഷം തുക വരുന്ന 3 പ്രവർത്തികളുടെയും Flood control Head ൽ ഉൾപ്പെടുത്തി 142 ലക്ഷം തുക വരുന്ന 5 പ്രവർത്തികളുടെയും പ്രൊപ്പോസൽ പരിശോധിച്ചുവരുന്നു. കൂടാതെ 605 ലക്ഷം തുകയുടെ "construction of Retaining Wall and rectification of damaged approach road for odajikkal RCB in Manpad panchayat in Malappuram district" എന്ന പ്രവർത്തിയുടെ പ്രൊപ്പോസൽ നമ്പാർഡിന്റെ സഹായത്തോടെ തയ്യാറാക്കിയിട്ടുണ്ട്. പ്രസ്തുത പ്രവർത്തികൾക്കായി തുക ഒന്നും തന്നെ ചെലവഴിച്ചിട്ടില്ല.</p>


 സെക്ഷൻ ഓഫീസർ

KERALA WATER AUTHORITY, P.H.CIRCLE , MALAPPURAM

List of works sanction obtained under Flood

Sl NO	Name of scheme	Description of work of work	AS amount in lakhs
1	1 ARWSS to Kavanoor	35 HP Submersible motor 2 Nos and their starter ,Panel Board and accessories submerged in water. The pump and accessories dismantled and undergo cleaning, drying and re erection	0.25
2	2 ARWSS to Urangattiri	The pump packing and starter contact damaged	0.21
3	3 ARWSS to Vazhakkad	30 HP Submersible motor 2 Nos and their starter ,Panel Board and accessories submerged in water. The pump and accessories dismantled and undergo cleaning, drying and re erection	0.39
4	4 MWSS to Malappuram, Hajiarpalli pump house	Dismantling, conveying, ,cleaning ,drying, re-erection, checking and testing 90 HP Motor 2 nos and allied accessories , Repair and replacement of damaged components of starter -2Nos,	1.28
5	5 MWSS to Malappuram, Kattungal pump house	Dismantling, conveying, ,cleaning ,drying, re-erection, checking and testing of starter -2Nos	0.41
6	6 MWSS to Malappuram, Nambrani pump house	Dismantling, conveying, ,cleaning ,drying, re-erection, checking and testing 100 HP Motor 2 nos and allied accessories , Repair and replacement of damaged components of starter -2Nos, .	1.26
7	7 NABARD aided WSS to Areekode	90 HP VT motor 2 Nos and their starter ,Panel Board and accessories submerged in water. The motor and accessories dismantled and undergo cleaning, drying and re erection	1.48
8	8 RWSS to Kalikavu	Electrical installation repairing works	0.39
9	9 RWSS to Kodur (Konkayam)	Cleaning of pump house	0.02
10	10 RWSS to Kodur (Konkayam)	Repair work to panel board and accessories.	0.30
11	11 RWSS to Kodur (Nooradi)	Cleaning of pump house	0.02
12	12 RWSS to Kodur (Nooradi)	Repair work to panel board and accessories.	0.45
13	13 RWSS to Koottilangadi	Cleaning of pump house	0.02
14	14 RWSS to Koottilangadi	Repair work to panel board and accessories.	0.27
15	15 RWSS to Mundayil padi	Cleaning of pump house	0.02
16	16 RWSS to Mundayil padi	Repair work to panel board and accessories.	0.67
17	17 RWSS to Padinjattumuri	Cleaning of pump house	0.02
18	18 RWSS to Padinjattumuri	Repair work to panel board and accessories.	0.57
19	19 RWSS to Pandikkadu	Pump house Cleaning	0.05
20	20 RWSS to Pandikkadu	Pump set, Electrical installation repairing works	1.03
21	21 RWSS to Unnamathala	Cleaning of pump house	0.02
22	22 RWSS to Unnamathala	Repair work to panel board and accessories.	0.33

23	23 Uwss to Amarambalam	Silt removing from distribution line at Puthiyakalam	0.25
24	24 Uwss to Mampad	Repair the pump set	0.25
25	25 UWSS to Perinthalmanna	Electrical installations, transformer repairing works	1.05
26	26 wss to Edakkara	Pump House Cleaning	0.05
27	27 wss to Edakkara	Repair to 45 HP Submersible pump set	0.15
28	28 WSS to Kannamangalam and WSS to Urakam & Vengara	Charges for conveying, lifting, erecting 2 nos. of open well type submersible pump set (10 HP from Chelari P/h & 5 HP from Tiruranagdi P/h with starter and other accessories and flexible hose to WTP of WSS to Kannamanagalam at Vengara	0.23
29	29 WSS to Kannamangalam and WSS to Urakam & Vengara	Repair work to the 150HP VT Pump set	1.50
30	30 wss to Padinjattumpadam	Pump House Cleaning	0.05
31	31 wss to Padinjattumpadam	Repairs to 15HP and 10HP starters and Electrical installation.	0.27
32	32 WSS to Thazhekode	Pump house and Tank cleaning	0.11
33	33 WSS to Tirurangadi(East)	Repair work to the starter	0.15
34	1. MWSS to Malappuram, chamakkayam pump house	Repair works to 2 Nos. 100 HP pumpset, damaged starter 4 Nos., repairs to OCB	3.00
35	2. RWSS to Mundayil padi	Replacing damaged 100 mm GI pipe	1.80
36	3. MWSS to Malappuram Hajiyarpalli pmp house	Repair to compound wall of OHSR and pump house	2.15
37	4. UWSS to Perinthalmanna	Reconstruction of damaged compound wall	2.25
38	5. WSS to Edakkara	Repairs to the well cum pump house and acces to the pump house	2.90
39	6. UWSS to Mampad	Repair work to the infiltration arrangement, desilting, repir work to the pump house	3.00
40	7. MWSS to Malappuram Mannarkundu pmp house	RR masonry (land sliding nera intake structure and drainage block)	4.00
41	8. UWSS to Nilambur	Temporary arrangements to protect WTP structure and office building due to land slide near by the treatment plant	10.00
42	9. UWSS to Nilambur	Constructuion of reatining wall for a length of 76.50 m to protect the structures and office building due to land sliding	220.00
43	10. UWSS to Thirur	Cleaning Transformer be moisterisation resetting etc.	0.150
44	11. Rws to Edarikkode - Thennala	Damaged water connection	0.300
45	12. Rws to Edarikkode - Thennala	Damaged water meter	0.150
46	13. Rws to Edarikkode - Thennala	Over hauling, cleaning ,drying,checking and testing 75 HP Motor	0.600
47	14. Rws to Edarikkode - Thennala	Over hauling, cleaning ,drying,checking and testingsubmersible pumps.	0.296

48	15.Rwss to Edarikkode - Thennala	Repaire and replacement of soft starter	0.200
49	16. RWss to Irumblium - Valancheri	Cleanig drying ,testing of CTPT.	0.200
50	17. RWss to Irumblium - Valancheri	Over hauling, cleaning ,drying,checking and testing 120 HP VT Motor	0.405
51	18.RWss to Irumblium - Valancheri	Over hauling, cleaning ,checking and testing VT pump	0.495
52	19.RWss to Irumblium - Valancheri	Repaire and replacement of damaged components of soft starter	1.47
53	20.Rwss to Kottakkal-Parappur	Damaged water connection	0.30
54	21.Rwss to Kottakkal-Parappur	Damaged water meter	0.15
55	22.Rwss to Kottakkal-Parappur	Desilting of well	0.85
56	23.Rwss to Kottakkal-Parappur	Over hauling, cleaning ,checking and testing Submersible Pump	1.25
57	24.Uwss to Ponnani and ARWSS to Ezhavathiruthi	200HP CF 1 No. Overhauling	0.77
58	25.Uwss to Ponnani and ARWSS to Ezhava thiruthi	200 HP CF 1 No. Rewinding seconed one and vaccoum pump repaires heating and overhauling.	1.46
59	26.Uwss to Ponnani and ARWSS to Ezhava thiruthi	Cleanig .	1.00
60	27.Uwss to Ponnani and ARWSS to Ezhava thiruthi	Removal of debris	1.00
61	28.UWSS to Tirur	Cleaning of pump house	0.10
62	29.CRWSS to Thirunavaya	Reconstruction of damaged damaged wall	0.20
63	30.DAWSS to Edappal & Adjoining PTS	Cleaning tank	0.04
64	31.DAWSS to Edappal & Adjoining PTS	Cleaning tank	0.35
65	32.DAWSS to Edappal & Adjoining PTS	Cleaning tank	0.25
66	33.DAWSS to Edappal & Adjoining PTS	Cleaning tank	0.25
67	34.DAWSS to Edappal & Adjoining PTS	Cleaning tank	0.16
68	35.DAWSS to Edappal & Adjoining PTS	Cleaning tank	0.15
69	36.DAWSS to Edappal & Adjoining PTS	UG cable work,CP-PT Meter replacement ,transformer oil changing	0.508
70	1.WSS to Cheekkode & Adjoining Villages	Construction of Damaged portion of Retaining wall	0.50
71	2.WSS to Kavanur Pts	Dis mantling and relaying of pipe line	0.50
72	3.WSS to Othukkungal and Ponmala pts	Repair work of 3 nos panel board	0.50
73	4.WSS to Thiruvalli and Adj pts	Slided sides of GLSR to be protected with retainin wall	3.50

74	5.WSS to Thiruvali and Adj pts	Procted the structure with retaining wall	28.50
75	6.WSS to Cheekkode & Adjoining Villages	Repair work of 3X3 nos of motor	3.88
		Grant total	313.05


മുഖ്യമന്ത്രിയുടെ കാര്യാലയം